Q60A/R

CONTROL UNIT FOR SWING GATE SINGLE OR DOUBLE LEAF 230V

EXTERNAL RADIO PANEL

THE RADIO PANEL CAN ALSO BE PLACED INSIDE THE BLINKER TO FURTHER IMPROVE THE RADIO RANGE



CONTROL UNIT COMPONENTS

A	TOP LEVEL MENU BUTTON
B	LOWER LEVEL MENU BUTTON
C	BUTTON TO INCREASE OR CHANGE TO YES (SI)
D	BUTTON TO DECREASE OR CHANGE TO NO
FI	230V FUSE 5A
F2	COCOON FUSESFUSE MOTOR 2 1,6 A
F3	COCOON FUSESFUSE MOTOR 1 1,6 A
F4	24V FUSE (SELF-RESTORABLE) 1,6A
F5	24V FUSE (SELF-RESTORABLE) 0,65A
DISPLAY	7 SEGMENTS DISPLAY
MI	RADIO/AERIAL TERMINAL BLOCK
M2A/M2B	CONTROLS AND SAFETY DEVICES TERMINAL BLOCKS
M3	MOTORS TERMINAL BLOCK
M4	MAIN POWER TERMINAL BLOCK
A B C	EARTH CONNECTIONS
MR	RADIO UNIT
CN	ELECTROLOCK INTERFACE PCB CONNECTOR
Z2	FILTER
KI/ K2	MOTORS RELAY
K3	BLINKER RELAY
VI	PRIMARY VARISTOR
V2	SECONDARY VARISTOR

09122004446
ArmaSystem

www.ArmaSystem.com

PARAMETERS

B use **button B** to move to next parameter
C use **button C** to **INCREASE** a numeric value or change **NO** to **YES**
D use **button D** to **DECREASE** a numeric value or change **YES** to **NO**
To save changes and to ensure that they are not lost when power is removed, use **button B** to step through SU parameter, the press and hold **button C** until the display reverts to idle display .

SELF-RESTORABLE FUSE 24V
IMPORTANT: IF A TEMPORARY SHORT CIRCUIT OCCURS THE FUSE **WILL RESTORE ITSELF AFTER FEW SECONDS.**

IN CASE OF A PERMANENT SHORT CIRCUIT, CUT THE MAIN POWER OFF, REMOVE THE TERMINAL BLOCKS 2A AND 2B, WAIT FEW SECONDS AND THEN POWER THE UNIT AGAIN.
THE FUSE WILL BE AUTOMATICALLY RESTORED.
FIND AND REMOVE THE SHORT CIRCUIT CAUSE BEFORE PLUGGING THE TERMINAL BLOCKS IN.

BUTTON A → CYCLE ROUND THE TOP LEVEL MENU
BUTTON B → MOVE FROM THE TOP LEVEL MENU TO THE LOWER LEVEL MENU
BUTTON C → INCREASE TIME OR CHANGE TO YES
BUTTON D → DECREASE TIME OR CHANGE TO NO



DISPLAY SIGNALS

AP	Opening
CH	Closing
tP	Delay time before automatic **Closing**

TOP LEVEL MENU

--	STAND BY
PA	PARAMETERS
rA	RADIO
dE	DEFAULT
AS	SEQUENTIAL PROGRAMMING

PARAMETERS

DISPLAY	TIMES	standard default values rP	Simply default values dS	Runner default values dr
n1	Motor 1 working time 0 → 99	21	13	9
n2	Motor 2 working time 0 → 99	21	13	9
F1	Motor 1 Torque 8 → 19	14	10	12
F2	Motor 2 Torque 8 → 19	14	10	12
Fr	Motor power during deceleration 10→ 19	19	19	19
r1	Motor 1 deceleration time 0 → (N1 - 2")	7	4	4
r2	Motor 2 deceleration time 0 → (N2 - 2")	7	4	4
tS	Motors' closing differential time delay 0 → N2	3	3	2
SA	Motors' opening differential delay time 0 → (N1 - r1)	3	3	2
tP	Delay time before automatic closing 0 → 99	3	3	3
Pd	Pedestrian opening time 0 → (N1 - r1)	7	7	3
tC	Lock pulse time 0=½ seconds, 1= 1 secs. 2=1½ secs. Etc.....	0	0	0

FUNCTIONS

	FUNCTIONS	STANDARD DEFAULT VALUES rP	SIMPLY DEFAULT VALUES dS	RUNNER DEFAULT VALUES dr
SU	PRESS & HOLD **BUTTON C** TO SAVE CHANGES PRESS **BUTTON D** TO ABANDON CHANGES	NO	NO	NO
P9	SOFT START	SI	SI	SI
P8	PHOTOCELLS TEST	SI	SI	SI
P7	MOTORS TEST	SI	NO	SI
P6	DECELERATION ON	SI	SI	SI
P5	ONLY ONE MOTOR	NO	NO	NO
P4	PRE BLINKING	NO	NO	NO
P3	AUTOMATIC CLOSING STEP BY STEP	SI	SI	SI
P2	MULTI OCCUPATION	NO	NO	NO
P1	ELECTRO LOCK	NO	NO	SI
P0	WATER HAMMER	NO	NO	NO

CODE FUNCTIONS

CODE	FUNCTIONS
r=	SHOW STORED CODES
tC	NEW REMOTE CONTROL CODE ACQUISITION
CP	REMOTE CONTROL CODE ACQUISITION WITH STOP FUNCTION
Pd	REMOTE CONTROL CODE ACQUISITION WITH PEDESTRIAN FUNCTION
rC	DELETE ALL REMOTE CONTROL CODES

CODE FUNCTIONS

CODE	FUNCTIONS
rP	PRESS & HOLD BUTTON C TO SET DEFAULTS FOR ASTER OR BLANK.
dS	SIMPLY MOTOR DEFAULTS PRESS & HOLD BUTTON C TO SET DEFAULTS FOR SIMPLY
dr	RUNNER DRIVE DAFAULTS PRESS & HOLD BUTTON C TO SET DEFAULTS FOR RUNNER

DISPLAY FUNCTIONS

DISPLAY	FUNCTIONS
1n	ONLY 1 MOTOR
2n	2 MOTOR

PROGRAMMING THE RADIO rA

IMPORTANT: BEFORE PROGRAMMING FOR THE FIRST TIME THE RADIO RECEIVER, DELETE ALL THE RECORDED TEST CODES. SEE FUNCTION rC AT THE BOTTOM OF THIS CHAPTER

IN CASE OF TRANSMITTERS WITH DIP-SWITCHES, SET THE MICROSWITCHES TO CREATE A NEW PERSONAL CODE.
(For security reasons avoid to set the microswitches all in OF or all in ON position).

IN CASE OF HIT TYPE TRANSMITTERS, THE ABOVE MENTIONED PROCEDURE IS NOT NECESSARY BECAUSE EACH TRANSMITTER COMES WITH ITS OWN CODE RANDOM.

r = **DISPLAYING STORED CODES**
Press the **button A** repeatedly until the display shows rA
Press **button B** until the display shows r =
The display will now cycle trough each stored code from 01 to 50.
TO ERASE A SINGLE STORES CODE
Press **button D** when the number of the code to be removed is displayed

tc **STORING NEW REMOTE CONTROL CODE**
- Press the **button A** repeatedly until the display shows rA
- Press **button B** until the display shows tc
- Press and hold the remote control button until a dot appears on the display (this means that the receiver is ready to store a new code) and simultaneously press **button C** to store the new code

CP **STORING NEW REMOTE CONTROL CODE with STOP function**
- Press the **button A** repeatedly until the display shows rA
- Press **button B** until the display shows CP
- Press and hold the remote control button until the dot appears on the display and simultaneously press **button C** to store the new code.

Pd **STORING NEW REMOTE CONTROL CODE with PEDESTRIAN function**
- Press the **button A** repeatedly until the display shows rA
- Press **button B** until the display shows Pd
- Press and hold the remote control button until the dot appears on the display and simultaneously press **button C** to store the new code

rC **DELETING ALL STORED CODES**
- Press the **button A** repeatedly until the display shows rA
- Press **button B** until the display shows rC
- Press and hold **button D** until the display shows r =
This indicates that all the codes have been erased

SELF-DIAGNOSIS DISPLAY MESSAGES

EF Photocell's test error	Co Start signal (short circuit between terminal 1 & 8)
tA Opening phase photocell beam interrupted or wiring fault	-.- Radio fob continuously transmitting
tC Closing phase photocell beam interrupted or wiring fault	n1 Motor 1 problem (wiring fault, obstruction or torque setting too low)
FH Both opening and closing phase photocell beam interrupted or wiring fault	n2 Motor 2 problem (see 'n1' above)
St Stop pressed (or open circuit between terminal 2 & 8)	nr Both motors problem (see 'n1' above)
PE Pedestrian start signal (short circuit between terminal 7 & 8)	

PROGRAMMING THE Q60A PARAMETERS PA

Method **1** = **STANDARD**
Method **2** = **SEQUENTIAL**

Warning:
Before powering up and programming the control unit refer to the wiring scheme and then:
1 Check that the motor connections are correct
2 Check that the photocell connections are correct
Important:
If the photocells are not installed in closing phase, you must link terminals 3 and 9.
If the photocells are not installed in opening phase, you must link terminals 4 and 9.
3 Check that the control connections are correct.
Important:
If an emergency stop button is not fitted, you must link terminals 2 and 8.
4 Use the motor release key supplied to disengage the electric motor from the mechanical drive; then close the gate and re-engage.
5 Power the control unit up

STANDARD PROGRAMMING PROCESS (*Method 1)*

a) Give a **START** signal by either turning the key s:witch or by another control device (terminals 1 and 8)
b) Wait until the gate has finished a complete (pre-programmed) **OPEN/STOP/WAIT/CLOSE** cycle.
c) Give another **START** signal and not which parameter need adjusting
d) Press **button A** on the control unit to select the Parameters menu.
e) Press **button B** repeatedly until the display shows the parameter that you need to change
f) Use **buttons C** and **D** to change or confirm each parameter as necessary
IMPORTANT: press **button B** repeatedly until the display shows SU and then press **button C** to save the changes.

Example:
Increase the **Motor 1** working time by **2 seconds**

With the control board switched on, ensure that the display shows: → - -
Press **button A** (steps thru the top menu) until the display shows → PA
Press **button B** (steps thru the sub-menu) until the display shows → t1
Wait until the display shows the currents setting, for example → 21
Press **button C** twice until the display shows → 23
Press **button B** repeatedly until the display shows → SU
Press and hold **button C** until the relays click and the display shows → - -

SEQUENTIAL PROGRAMMING (*method 2)*

SEQUENTIAL programming for gates with only one leaf

a) Press **button A** (steps thru the top menu) until the display shows AS
b) Press **button B** (steps thru the sub-menu) until the display shows in1
c) Give a **START** signal: the leaf starts opening and the display shows in1
d) Wait until the leaf has done the 90% of the opening cycle and then give another **START** signal: the display shows r1 and the deceleration phase begins
e) Wait 4/5 seconds after the opening cycle has completely finished and give a **START** signal.
f) The display shows tP, the control unit has stored the opening and deceleration times and is now calculating the **"stay open"** time
g) Give a **START** signals to stop calculating the **"stay open"** time and start the **CLOSING CYCLE**.
g) When the closing cycle has completely finished, the control unit automatically exits from the sequential programming process and all the working times have been saved.

SEQUENTIAL programming for gates with two leaf

a) Press **button A** (steps thru the top menu) until the display shows AS
b) Press **button B** (steps thru the sub-menu) until the display shows 2in
c) Give a **START** signal:
The leaf 1 starts opening and the display shows in1
d) Wait until the **leaf 1** has done the 90% of the opening cycle and then give another **START** signal: the display shows r1 and the deceleration phase of **leaf 1** begins
e) Wait 4/5 seconds after the **leaf 1** has completely opened and give another **START** signal. The display shows in2 and the **leaf 2** starts opening
f) Wait until the **leaf 2** has done the 90% of the opening cycle and then give another **START** signal: the display shows r2 and the deceleration phase of **leaf 2** begins
g) Wait 4/5 seconds after the **leaf 2** has completely opened and give another **START** signal.
h) The display shows tP, the control unit has stored the opening and deceleration times of both leaves and is now calculating the **"stay open"** time
i) Give a **START** signals to stop calculating the **"stay open"** time and **start the closing cycle**.
l) When the **closing cycle** has completely finished, the control unit automatically exits from the sequential programming process and all the working times have been saved.

SPECIAL FUNCTIONS

P3 **AUTOMATIC CLOSING FUNCTION**
When set to YES ("SI"):
- an impulse during the opening phase will stop the motors until another impulse is received
- an impulse during the closing phase will stop and reverse the motors

When set to NO, the step-by-step operation is active:
- 1st impulse starts the **opening phase**
- 2nd impulse stops the **opening phase**
- 3rd impulse starts the **closing phase**

P2 **MULTI-USER FUNCTION**
when set to **YES** ("SI"):
The control unit will not accept any command during the opening phase





4 to 9
3 & 9 to NC & COM





TERMINAL BLOCK CONNECTIONS

All the connections must be done without power supply.

EARTH TERMINAL BLOCK CONNECTIONS

Connect the yellow/green network cable and the yellow/green motor cables to earth terminals **A B C**.

TERMINAL BLOCK 2 CONNECTIONS

1-8	**Start control** normally open (NA) for button, key selector, radio receiver or Timer clock connections. The Start control starts the programmed running cycle.
2-8	**Stop control** normally closed (NC). Emergency button. When pressed the gate stops immediately. In Opening phase: at the first impulse the gate closes. Break-time: at the first impulse the gate closes In Closing phase: at the first impulse the gate opens. **If temporarily the Stop contact is not used, link terminal 2 with terminal 8.**
3-8	**Input of one safety photocell in closing phase.** **Input of safety rubber edges and of safety photocell in closing phase.** **Input of several safety photocells in closing phase**. The receiver contacts must be connected in series. Normally closed (NC). In opening phase: does not work In closing phase: Stop, break-time for 2 seconds, opening phase again. **If temporarily the photocell contacts are not used, link terminal 3 with terminal 9.**
3-9	**Input only for safety rubber edges in closing phase.** The contacts must be connected in series if there is more than one safety rubber edge. Normally closed (NC). In opening phase: does not work. In closing phase: Stop, break-time for 2 seconds, opening phase again.
4-8	**Input for safety photocells in opening phase (for swing gate).** Normally closed (NC). In opening phase: Stops until the obstacle has not been removed In closing phase: Stops and changes direction when the obstacle has been removed If you also want to connect the safety rubber edges, you must connect in series their contacts with the photocell ones. **If temporarily the photocell contacts are not used, link terminal 4 with terminal 9.**
4-9	**Input for safety rubber edges in opening phase (for swing gate).** Normally closed (NC). In opening phase: Stops until the obstacle has not been removed In closing phase: Stops and changes direction when the obstacle has been removed The contacts should be connected in series.
7-8	**Pedestrian start input**. Normally open (NA).
8-10	**Output for photocell receiver power supply.** **Output for extra 24V dc accessories power supply.** With all Standard accessories included 100 m A are still available for extra accessories.
9-10	**Output for photocell transmitter power supply.**
11-12	**Blinker intermittent output.** 24V 20W max.

TERMINAL BLOCK 3 CONNECTIONS

13-14-15	**Motor M1- output** Leaf that opens firstly and that delays in closing phase. In case of a gate of one single leaf connect the motor to output **M1**, select parameter P5 on SI, confirm with SU and save with push **button C**. CAPACITOR between terminal 13 and 15
16-17-18	**Motor M2- output** Leaf that opens secondly. CAPACITOR between terminal 16 and 18

TERMINAL BLOCK 4 CONNECTIONS

19-20	Power input 230-240 Vac - 50/60 Hz. (19=Neutral - 20=phase)

WIRING SCHEME FOR THE Q60A NEW CONTROL UNIT

1 START



2 PEDESTRIAN START



3 PERMANENT START COMMAND WITH TIMER





4 EMERGENCY STOP BUTTON



N.B.: Link terminals **2** and **8** if, an emergency **STOP** button is NOT USED.



5 MOTORS CONNECTIONS

MyAster
First opening leaf, **RIGHT**







First opening leaf, **LEFT**



ONE MOTOR ONLY (RIGHT) CONNECTION



ONE MOTOR ONLY (LEFT) CONNECTION



MyHook
First opening leaf, **RIGHT**



First opening leaf, **LEFT**



ONE MOTOR ONLY (RIGHT) CONNECTION



ONE MOTOR ONLY (LEFT) CONNECTION



MyShark

First opening leaf, **RIGHT**





First opening leaf, **LEFT**





ONE MOTOR ONLY (LEFT) CONNECTION



ONE MOTOR ONLY (RIGHT) CONNECTION



MyFlow

First opening leaf, **RIGHT**





First opening leaf, **LEFT**





ONE MOTOR ONLY (RIGHT) CONNECTION



ONE MOTOR ONLY (LEFT) CONNECTION



6 CONNECTING PHOTOCELL IN CLOSING PHASE



PHOTOCELLS CONNECTIONS

8 = Power supply + PHOTO RX
9 = Power supply + PHOTO TX
10= Power supply - COM. PHOTO TX/RX

3 - 8 = Photocells connection

3 - 9: Link terminals **3** and **9** if the photocells are not used in the closing phase.



CONNECTING PHOTOCELL IN OPENING PHASE



PHOTOCELLS CONNECTIONS

8 = Power supply + PHOTO RX
9 = Power supply + PHOTO TX
10= Power supply - COM. PHOTO TX/RX

4 - 8 = Photocells connection

4 - 9: Link terminals **4** and **9** if the photocells are not used in the opening phase.



7 ELECTRO-LOCK INTERFACE BOARD(MEL)

IF YOU WANT TO CONNECT THE **MEL** INTO **CN**
- CONNECT THE ELECTRO LOCK
- CHANGE THE PARAMETERS P0 - P1 AND tC